


Sorting Center

Date: 2021

Location: Plymouth, MI

Advantage: Cost Savings



Technical Specifications

Fiber Reinforcement: FORTA-FERRO[®] 2-1/4"

Application: Slab-on-Ground

Dosage: 4.0 lb/cu yd

Delivery Method: Pumped

Finish Method: Steel-Troweled; Broomed

FORTA-FERRO macro synthetic fibers were used in this newly constructed sorting center. Owners saw substantial **cost savings** and **increased job-site safety** due to the elimination of wire mesh or steel rebar.



World-class design services, on-site support. Contact us to learn more.