

Fillmore County Overlay

Date: 2023

Location: Lanesboro, MN

Advantage: Cost Effective,
Reduced Construction
Time



Croell, Inc.
www.croell.com



Technical Specifications

Application: Overlay

Fiber Reinforcement: FORTA-FERRO[®] 2-1/4"

Dosage: 4.0 lb/cu yd

Delivery Method: Tailgated

Finishing Method: Heavy Broomed



The contractor was able to **reduce time and material** by **eliminating the steel** from this project. Their paving machine was able to install a beautiful, groomed finish as fast as the concrete could be delivered without stopping to install steel. Croell added the fibers at their mobile batch plant directly from large containers or gaylord's **saving them time and waste at the batch plant.**



World-class design services, on-site support. Contact us to learn more.