



FULFILLMENT CENTER - NORTH RANDALL, OH

PROJECT DESCRIPTION

A large fulfillment center in North Randall, OH spanned 23,000 cu yd with a fiber dosage of 7.5 lb/cu yd. The contractors specified FORTA-FERRO macro synthetic fibers to be used in this design. The fiber reinforced concrete was easily pumped up to the multiple slab-on-metal-deck levels. This **allowed the contractor to complete around 500 yd every couple of days** which would not have been possible if steel reinforcements were used. The FORTA-FERRO fibers **provided durability** to the concrete **controlling any future cracking**.

KEY POINTS

- Reduced Shrinkage Cracking
- Save Time
- Increase Durability

DETAILS

Date: 2018

Location: North Randall, OH

Dosage: 7.5 lb/cu yd

Fiber: FORTA-FERRO® 2-¼"

Contact us for more details